

INFORMA - By Actiu -

Informa Programme	02
Technical details	04
How to do different Informa layouts	07
End Leg packs and end panel packs	07
How to end reception counter configurations	08
Rectangular modules 75cm	09
Rectangular modules 150cm	12
Curved modules 45°	15
Curved modules 90°	18
Low reception modules for disable people attending	20
Low reception modules	21
Low reception modules for progressive use	22
Conference Tables	23
Pack of end panels for conference table	23





Reception Counters



■ FRAME



- **Bottom, middle and top beam:** extruded aluminium 1,5mm, 40x60 mm profile. Epoxy finish. Moulded aluminium arms to fix shelves and worktops.
- Legs: Extruded aluminium legs. Epoxy finish silver (2 mm thickess). Two heights: 107 cm for high reception modules and 73cm for attending area modules for disable people.
- (3) Feet: Moulded aluminium feet. Epoxy finish. Silver. Each foot includes two levellers with anti-skid pad of Polyethylene (PE).

INFORMA ACCESSORIES





Cable management:

Informa includes ABS silver cable channels fixed to the beams to get comfortable and correct cable management. Dark grey finished.



Foot rest included with the lower beams to provide extra comfort and protection for the metal beam.



End Panels: (optional)

Informa includes end panels to avoid seeing what there is inside the counter, legs, cables...

■ SURFACES FINISHES



(see finishes card)





■ FRONT FINISHES

Steel Panel (1,5 mm)



Kiwi

Strawberry

Natural Oak





Wengue Oak

Finishing will be discontinued once the stock finished.



Conference Tables



■ ESTRUCTURA



- 1) Bottom and top beam: extruded aluminium 1,5mm, 40x60 mm profile. Epoxy finish. Moulded aluminium arms to fix shelves and worktops.
- (2) Legs: 73cm Extruded aluminium legs. Epoxy finish silver (2 mm thickess).
- **Feet:** Moulded aluminium feet. Epoxy finish. Silver. Each foot includes two levellers with anti-skid pad of Polyethylene **(PE)**.

■ INFORMA ACCESSORIES





Cable management:

Informa includes ABS silver cable channels fixed to the beams to get comfortable and correct cable management.

Dark grey finished.



Foot rest

Foot rest included with the lower beams to provide extra comfort and protection for the metal beam.



End Panels: (optional)

Informa includes end panels to avoid seeing what there is inside the counter, legs, cables...

■ WORKTOP FINISHES

Melamine (25 mm)



(see finishes card)

FRONT FINISHES

Steel Panel (1,5 mm)



(see finishes card)





MATERIALS

Maximum use of materials to eliminate and minimize scraps. Use of recyclable and recycled materials in those components that do not affect the functionality and durability.

62,37%



PRODUCTION

Maximum optimization of energy use. Minimal environmental impact. Last generation technological systems. Zero discharge of wastewater. No VOC coatings. Processes free of heavy metals, phosphates, OC and COD.

100% RECYCLABLE ALUMINIUM, STEEL & WOOD



TRANSPORT

Detachable systems. Volumes that facilitate the optimization of space. Maximum reduction of energy consumption by transport.

100% RECYCLABLE PACKAGE AND THINNER FREE



USE

Quality and warranty. Long lasting. Replacements available.

EASY TO CLEAN AND MAINTAIN



DISPOSAL

Waste reduction. Supplier-manufacturer packaging reuse system. Components are easy to be separated. Inks in packaging are water-based, without solvents.

98,12% RECYCLABLE MATERIALS

■ CERTIFICATES AND REFERENCES

The different programmes get points in different environmental categories to get the LEED certificate (sustainability, material and resources, water, energy and atmosphere, inner environment quality, innovation and design).



The mark of



PEFC Certificate



EN ISO 14006:2011
ECODESIGN Certificate



UNE-EN ISO 9001:2008 ISO 9001 Certificate



UNE-EN ISO 14001:2004 ISO 14001 Certificate



E1 Certificate by EN 13986



ACTIU TECHNOLOGY PARK LEED® PLATINUM certified by USGBC Leadership in Energy & Environmental Design LEED® Gold certified 2011 - LEED® Platinum certified 2017